

### Annexure-A: Retrofitting Cost Chart for Preliminary Estimate

1.	Cost of column jacketing with footing jacketing (Sub-structure + Ground Floor)	Tk. 71,098.00	Per Meter of Column
2.	Cost of column jacketing only (up to Plinth + Ground Floor)	Tk. 47,029.00	Per Meter of Column
3.	Cost of shear wall with footing (Sub-structure + Ground Floor)	Tk. 57,223.00	Per Sqm of Shear Wall
4.	Cost of sub-structure for steel bracing	Tk. 38,386.00	Per Sqm of Frame
5. a	Cost of column jacketing work (from 1 <sup>st</sup> floor and above)	Tk. 42,686.00	Per Meter of Column
5.b	Add cost for each additional floor	1.5%	of Previous Floor
6.a	Cost of beam jacketing work	Tk. 49,502.00	Per Meter of Beam
6.b	Add cost for each additional floor	1.5%	of Previous Floor
7.a	Cost of shear wall (from 1 <sup>st</sup> floor and above)	Tk. 22,667.00	Per Sqm of Shear Wall
7.b	Add cost for each additional floor	1.5%	of Previous Floor
8.a	Cost of steel bracing work in-fill steel brace	Tk. 94,151.00	Per Sqm of Frame
8.b	Add cost for each additional floor	1.5%	of Previous Floor
9.a	Cost of steel bracing with beam- column extension	Tk.122,672.00	Per Sqm of Frame
9.b	Add cost for each additional floor	1.5%	of Previous Floor
10.a	Cost of Steel Bracing with Beam Extension	Tk. 107,246.00	Per Sqm of Frame
10.b	Add cost for each additional floor	1.5%	of Previous Floor