

CHAPTER 25 : ARBORICULTURE WORKS

Item No.	Description of Item	Unit	Unit Rate (Dhaka, Mymensingh)	Unit Rate (Chattogram, Sylhet)	Unit Rate (Khulna, Barisal, Gopalganj)	Unit Rate (Rajshahi, Rangpur)
25.1	Labour charge for scraping lawn surface up to 38 mm depth by spade, picking up all sorts of brick bats, rubbish by suitable tools, removing the same by head load or by any other means and stacking the same to a safe distance beyond 300 m including supply of tools and plants etc. all complete and accepted by the Engineer-in-charge.	sqm	Tk. 12.00	Tk. 12.00	Tk. 11.00	Tk. 11.00
25.2	Preparation of ground to make ready for plantation by spading the ground to a depth of 150 mm to 230 mm beyond 38 mm deep scrapped ground by spade, breaking earth clods to powder by hammers, picking up all sorts of rubbish, unwanted grasses by suitable tools, carrying and spreading the surplus earth into low lying area including supply of tools and plants etc. all complete and accepted by the Engineer-in-charge.	sqm	Tk. 24.00	Tk. 23.00	Tk. 21.00	Tk. 21.00
25.3	Leveling and dressing of lawn area to proper slope and grade by spading the same including supplying tools and plants etc. all complete and accepted by the Engineer-in-charge.	sqm	Tk. 8.00	Tk. 8.00	Tk. 8.00	Tk. 8.00
25.4	Supply of best and approved quality alluvial loamy silty soil including loading, unloading at both ends, properly stacking at site including supply of tools and plants etc. all complete and accepted by the Engineer-in-charge.	cum	Tk. 913.00	Tk. 910.00	Tk. 900.00	Tk. 900.00
25.5	Supply well decomposed cow dung carried by trucks or any other means including loading, unloading at both ends, stacking the same at site including supply of tools and plants etc. all complete and accepted by the Engineer-in-charge	cum	Tk. 1,703.00	Tk. 1,702.00	Tk. 1,649.00	Tk. 1,649.00
25.6	Labour charge for spreading the alluvial loamy silty soil from the stacks at site on the lawn surface, leveling, dressing the same including supply all necessary tools and plants etc. all complete and accepted by the Engineer-in-charge.	cum	Tk. 194.00	Tk. 190.00	Tk. 176.00	Tk. 176.00
25.7	Added rate for lifting alluvial loamy silty soil/ decomposed cow dung work in additional floor:					
25.7.1	Add for each additional floor up to 5th floor	cum	Tk. 83.00	Tk. 82.00	Tk. 76.00	Tk. 76.00
25.7.2	Add for each additional floor from 6th floor to 9th floor	cum	Tk. 119.00	Tk. 117.00	Tk. 108.00	Tk. 108.00
25.7.3	Add for each additional floor for 10th floor & above	cum	Tk. 155.00	Tk. 152.00	Tk. 141.00	Tk. 141.00
25.8	Supply of lawn grass of approved quality by truck or by any other means, sorting the grass to proper size, washing the grass, dibbling the grass 6 mm to 50 mm apart, irrigation of lawn area till the grass grown at least for two months after plantation, weeding the undesirable grass, mowing the lawn grass by lawn mower up to two months after plantation, applying urea fertilizer on the lawn surface @ 1 kg per 9.29 sqm including supply of tools and plants etc. all complete and accepted by the Engineer-in-charge.	sqm	Tk. 67.00	Tk. 66.00	Tk. 62.00	Tk. 62.00
25.9	Labour charge for mixing well decomposed cow dung with alluvial loamy silty soil and excavated earth, removing the excess earth to safe distance including supply of tools and plants etc. all complete and accepted by the Engineer-in-charge.	cum	Tk. 175.00	Tk. 172.00	Tk. 159.00	Tk. 159.00

Handwritten signature or mark.

Handwritten signatures and marks at the bottom of the page.

Item No.	Description of Item	Unit	Unit Rate (Dhaka, Mymensingh)	Unit Rate (Chattogram, Sylhet)	Unit Rate (Khulna, Barisal, Gopalgonj)	Unit Rate (Rajshahi, Rangpur)
25.10	Supplying and providing, fitting & fixing bamboo jafry fencing by best quality muli bamboo split of 20 mm in width, having 75 mm x 75 mm mesh placed diagonally doing framing a square shape in both ways and both sides tightened with 2 x 4 Nos. same split horizontally and 2 x 6 Nos. same split vertically and with G.I wire fitted with Borrak bamboo post of 100 mm dia and placed firmly in position at 1800 mm apart including supply of tools and plants, digging hole and filling back etc. all complete and accepted by the Engineer-in-charge.	sqm	Tk. 550.00	Tk. 550.00	Tk. 535.00	Tk. 535.00
25.11	Supplying and providing, fitting & fixing muli bamboo tree guard of 1200 mm length and 500 mm dia best quality muli bamboo split 20 mm in size having 75 mm x 75 mm a square holes with 20 mm wide bamboo splits strengthen with 4 Nos. 20 mm wide bamboo split in both sides tightened with G.I wire fitted with 3 Nos. 63 mm dia borrak bamboo post of 1800 mm long of which 600 mm will be driven into earth by digging hole followed by fill back including supply of tools and plants all complete as per direction of the Engineer-in-charge.	each	Tk. 782.00	Tk. 782.00	Tk. 770.00	Tk. 770.00
25.12	Earth work in excavation to make a pit of 600 x 600 x 450 mm (depth) for plantation, applying cow dung mixing with loamy silty soil and excavated earth, planting the plants, tightened with 1800 mm long borrak bamboo post with jute rope and filled up the hole with mixed soil including supply of tools and plants all complete and accepted by the Engineer-in-charge.	each	Tk. 170.00	Tk. 169.00	Tk. 164.00	Tk. 164.00
25.13	Spading for preparation of flower beds in pits up to 600 mm depth, re-molding, picking up and placing and removing the spaded earth to a safe distance, mixing @ 1 cft well decomposed cow dung with 20% loamy silty soil and 6 cft excavated soil and fill back the pit including supply of tools and plants, all complete and accepted by the Engineer-in-charge.	sqm	Tk. 567.00	Tk. 562.00	Tk. 534.00	Tk. 534.00
25.14	Preparation of hedge beds by excavation of earth up to 300 mm depth, filling up the bed by a mixture of cow dung, loamy silty soil, cutted earth @ 1 cft cow dung manure per 6 cft of cutted earth and 20% loamy silty soil including supply of tools and plant etc. all complete and accepted by the Engineer-in-charge.	sqm	Tk. 280.00	Tk. 278.00	Tk. 264.00	Tk. 264.00
25.15	Carrying of rubbish , taking up all sorts of bricks, brick-bats and rubbish gravel chips, loading and unloading at both ends including supply of tools and plants etc. all complete and accepted by the Engineer-in-charge.	cum	Tk. 178.00	Tk. 175.00	Tk. 162.00	Tk. 162.00
25.16	Supply and carrying of 12.20 m long 100 mm dia borrak bamboo at site, loading and unloading at both end, stacking the same at site including supply of tools and plants etc. all complete and accepted by the Engineer-in-charge.	each	Tk. 537.00	Tk. 537.00	Tk. 534.00	Tk. 534.00
25.17	Supply and carrying of 7.62 m long 50 mm to 62.5 mm dia muli bamboo at site, loading and unloading at both end, stacking the same at site including supply of tools and plants etc. all complete and accepted by the Engineer-in-charge.	each	Tk. 284.00	Tk. 283.00	Tk. 281.00	Tk. 281.00

A collection of handwritten signatures and initials in blue ink, including names like 'Ruhana', 'S. S.', 'AA', and others, along with some scribbles and marks.

Item No.	Description of Item	Unit	Unit Rate (Dhaka, Mymensingh)	Unit Rate (Chattogram, Sylhet)	Unit Rate (Khulna, Barisal, Gopalganj)	Unit Rate (Rajshahi, Rangpur)
25.18	Supply and carrying of 4.5 h.p., 550 mm blade 4 stroke, finger trip 3 position height adjuster 200 mm x 38 mm star tread wheels grass cutting (Power Lawn Mower Machine): YARDMAN No. 060A	each	Tk. 54,335.00	Tk. 54,335.00	Tk. 54,335.00	Tk. 54,335.00
25.19	Supply and carrying of 6.5 h.p., 550 mm blade 4 stroke, finger trip 3 position height adjuster 200 mm x 38 mm star tread wheels grass cutting (Power Lawn Mower Machine): YARDMAN No. 060A	each	Tk. 72,447.00	Tk. 72,447.00	Tk. 72,447.00	Tk. 72,447.00
25.20	Supply and carrying of 22 h.p. 1150 mm cutting blade power riding lawn yardman mower machine made in USA. Model No.13 BT 793G678 or equivalent.	each	Tk. 591,082.00	Tk. 591,044.00	Tk. 590,890.00	Tk. 590,890.00
25.21	Supply and carrying of 450 mm blade Hand Lawn Moar, Model No.1403-106(USA)	each	Tk. 15,093.00	Tk. 15,093.00	Tk. 15,093.00	Tk. 15,093.00
..... END OF CHAPTER TWENTY FIVE						